BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

SCHEDULE - B

Name of work: Estimate for Improvements to Roads and Drains at Hegadenagara Near Ganesha Temple in Ward No.06, Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Rates Quoted by Contractor	
				In Figures	In Words
1	53.20	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1,P. No. 5/ Item No. 2.1/ PWD SR 2011-12	cum	126.98	Rupees One Hundred Twenty Six And Paise Ninety Eight Only
2	156.75	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to **wet mix macadam** specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406, No. 166/ Item No. 20.18/ PWD SR 2011-12	Cum	1114.51	Rupees One Thousand One Hundred Fourteen And Paise Fifty One Only
3	1045.00	KSRRB 500-4: providing and applying **primer coat** from 7.5 to 9.8 kg and 9.8 to 12.2kg per 10 sqm for surfaces of low and medium porosity respectively over prepared surface of granular base with cut bank M.C-70 or any other bitumen mixed with diesel at 10 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications MORTH chapter 5, No. 171/ Item No. 21.4.2/ PWD SR 2011-12 Medium Porosity	**Sqm**	87.49	Rupees Eighty Seven And Paise Forty Nine Only
4	26.13	KSRRB M500-18: Providing and laying **semi dense bituminous concrete 25mm thick** with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. 25-30mm compacted thikness with 5% Birumen80/100grade (gradingII) P.No. 174/ Item No. 21.20.1/ PWD SR 2011-12	Cum	9324.66	Rupees Nine Thousand Three Hundred Twenty Four And Paise Sixty Six Only
	68.10	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123,		70.67	Rupees Seventy And Paise Sixty Seven Only

Contractor Signature

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92